

Tabele robót ziemnych dla robót przy obiektach mostowych.

Droga powiatowa nr 3751W w miejscowości Kisielewo							
km	odległość	wykop	nasyp	średnia objętość		objętość suma	
				wykop	nasyp	wykop	nasyp
303,7		2,686	4,301				
	25,7			2,9555	8,481	75,95635	217,9617
329,4		3,225	12,661				
	37,5			3,8935	23,3605	146,0063	876,0188
366,9		4,562	34,06				
	0			0	0	0	0
380,2		5,308	47,49				
	19,8			4,3255	34,004	85,6449	673,2792
400		3,343	20,518				
	43			3,1715	11,859	136,3745	509,937
443		3	3,2				
suma [m3]						<b>443,982</b>	<b>2277,197</b>

Droga powiatowa nr 6914W w miejscowości Gołocin							
km	odległość	wykop	nasyp	średnia objętość		objętość suma	
				wykop	nasyp	wykop	nasyp
2564,2		2,01	3,316				
	34,1			2,115	2,1765	72,1215	74,21865
2598,3		2,22	1,037				
	2,7			2,22	1,037	5,994	2,7999
2601		2,22	1,037				
	11,62			0	0	0	0
2612,62		2,127	1,647				
	3,58			2,127	1,647	7,61466	5,89626
2616,2		2,127	1,647				
	46,8			1,9865	2,4285	92,9682	113,6538
2663		1,846	3,21				
suma [m3]						<b>178,6984</b>	<b>196,5686</b>